

June 9, 2020

## ***SUPPLEMENTAL/ BID BULLETIN***

**NAME OF THE PROJECT: CONTRACT FOR THE SUPPLY AND DELIVERY OF ONE (1) UNIT ASSEMBLY MOULDED CASE CIRCUIT BREAKER AND ONE (1) ASSEMBLY AUTOMATIC TRANSFER SWITCH (ATS) INCLUDING INSTALLATION, TESTING, AND COMMISSIONING**

This Addendum No. 1 is issued to modify or amend the Section 1 - Invitation To Bid, Section III- Bid Data Sheet, Section VI- Schedule of Requirements and Section VII- Technical Specifications of the Bidding Documents, and Invitation to Bid No. 023-2020 and Checklist of Requirements for Bidders under the CONTRACT FOR THE SUPPLY AND DELIVERY OF ONE (1) UNIT ASSEMBLY MOULDED CASE CIRCUIT BREAKER AND ONE (1) ASSEMBLY AUTOMATIC TRANSFER SWITCH (ATS) INCLUDING INSTALLATION, TESTING, AND COMMISSIONING. This shall form an integral part of the Bidding Documents.

### **Amended Section 1 - Invitation To Bid:**

Delivery of the Goods is required within Seventy (70) calendar days from receipt of Contract, Purchase Order (PO), and Notice to Proceed (NTP).

### **Amended Section III- Bid Data Sheet:**

12.1(a)	15. Duly signed Production/Delivery schedule indicating its commitment to deliver the Goods within 70 calendar days from receipt of the Contract, Purchase Order and Notice to Proceed;
---------	---

### **Amended Section VI- Schedule of Requirements:**

Item Number	Description	Quantity	Total	Delivered, Weeks/Months
1	<p>Main ECB 3000AT, 3Phase+G, 460V National Electrical Manufacturers Association (NEMA 1) (FREE STANDING) MOULDED CASE CIRCUIT BREAKER</p> <ul style="list-style-type: none"><li>• 1 – 3000AT 3 Pole 65-85kaic@ 460 Vac</li><li>• with MICROLOGIC 2.0A AMMETER; POWER METER</li><li>• Components Includes: LS Molded Case Circuit Breaker Fixed Type</li><li>• With extended busbar and lugs</li><li>• Mount in NEMA 1 wall mounted powder coated paint enclosure</li><li>• Including Installation, Testing, and Commissioning</li></ul>	One (1) Assembly	One (1) Assembly	Within 70 Calendar Days from receipt of Contract, Purchase order and Notice to Proceed

2	<p>Automatic Transfer Switch (ATS) 3000AT, 85KSIC, 460V, 3P, 60Hz</p> <ul style="list-style-type: none"> <li>• 2- 3000AT 3 Pole 65-85kaic@ 460 Vac</li> <li>• LSIG 6A</li> <li>• Components Include: LS Air Circuit Breaker (ACB) Draw-out type with built-in geared motor, electrical and mechanical interlock, busbars and lugs.</li> <li>• Wired in NEMA 1 Free standing powder coated wrinkled gray enclosure.</li> <li>• Including Installation, Testing, and Commissioning</li> </ul>	One (1) Assembly	One (1) Assembly	Within 70 Calendar Days from receipt of Contract, Purchase order and Notice to Proceed
3	500 mm2 THW Stranded Copper Wire	One Hundred Twenty (120) Meters	One Hundred Twenty (120) Meters	Within 70 Calendar Days from receipt of Contract, Purchase order and Notice to Proceed
4	500 mm2 Mechanical LUGS; Two-Conductor	Twenty- Four (24) Pieces	Twenty- Four (24) Pieces	Within 70 Calendar Days from receipt of Contract, Purchase order and Notice to Proceed

**Amended Section VII- Technical Specification:**

1	<p><b>Main ECB 3000AT, 3Phase+G, 460V National Electrical Manufacturers Association (NEMA 1) (FREE STANDING) MOULDED CASE CIRCUIT BREAKER</b></p> <ul style="list-style-type: none"> <li>• 1 – 3000AT 3 Pole 65-85kaic@ 460 Vac</li> <li>• with MICROLOGIC 2.0A AMMETER; POWER METER</li> <li>• Components Includes: LS Molded Case Circuit Breaker Fixed Type</li> <li>• With extended busbar and lugs</li> </ul>
---	--

For guidance and information of all concerned.

**ATTY. DANTE A. ARCANGELES**

Chairperson

Bids and Awards Committee